552

BANGALORE DIVISION.

ADVERTISEMENT.

The 8th June 1891.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 27th June 1891, for improving Vartur Tank, Registered No. 321, Bangalore Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1892.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 12 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving Vartur Tank," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Improving Vartur Tank, Registered No. 321, *Bangalore Taluk.*

Sub-Heads.	Per.	Quantity.
Head Works and right bund, left Waste Weirs and Sluice.		
Earthwork	C. Yd.	3,710
Picking ground below jack bund and benching slopes	S. Yd.	6,090
Old stone work	C. Yd.	890
New stone work (burnt stone)	Do	540
Turfing slopes of jack bund	Sq. Yd.	6,090
Grade stones, new	No.	10
Taking and refixing old stone with new foot slabs	Do	54
R. No. stones	Do	1
Gauge stones 18 ft in length including fixing	Do	1
B. M. stones	Do	2
Bricks in surki mortar..	C. Ft.	1,106
Removing and refixing old slabs	Sq. Ft.	413
New slabs	Do	90
Concrete	C. Ft.	342
Plastering	Sq.	9·69
Old stone work to wing	C. Yd.	80
Sundry repairs to apron	Item.	2
Clearing approaches (earth being sandy could not be used for bund) ..	C. Yds.	6,875
Examining and repairing sluice	Item.	1
No. II.—Left Channel including relieving weir and accommodations.		
Earthwork	C. Yd.	6,600
Sundry jobs (such as opening out natural weirs, clearing site, &c.)	Item.	1
Bed grade stones with foot slabs 2′ × 1′ including fixing	No.	46
Index stones of spoil bank, &c. do do	Do	30
Bank grade stones	Do	44
Furlong stones with .. do do	Do	15
Mile stones with .. do do	Do	2

Sub-Heads.	Per.	Quantity.
Sluice No. stones	No.	4
Painting index stones of spoil bank	Do	30
Furlong stones	Do	15
Painting mile stones	Do	2
Do sluice No. stones	Do	4
Trimming spoil bank	Mile.	1 7/8
Earthwork (hard soil)	C. Yds.	2,235
Bricks in surki mortar	C. Ft.	3,301
Stone slabs, 3" thick	S. Ft.	359
Do 6" do	Do	523
Plastering with surki	Sq.	11·84
Rough stone work (burnt stone 3 miles lead)	C. Yds.	337
Clearing site	Item.	3
Clearing of approaches	Do	1
Baling water	Do	1
Earthwork	C. Yds.	46
Concrete	C. Ft.	30
Rough stone work	C. Yds.	11
Earthwork	Do	280
Turfing	Sq. Yds.	7·10
Grade stones	No.	8
Stone slabs, 4½" thick	S. Ft.	93
Iron rails, each 20 ft., including cartage	No.	2
Slabs sluices as per type design	Do	4
No. III.—Right channel including over superpassages and one accommodation tunnel.		
Earthwork	C. Yds.	12,320
Sundry jobs	Item.	1
Bed grade stones with Ft. slabs, 2′ × 1′, including fixing	No.	85
Index stones of spoil bank	Do	81
Mile stones with do	Do	4
Sluice No. stones	Do	7
Mile stones	Do	4
Sluice No. stones	Do	7
Trimming spoil bank	Miles.	3½
Earthwork	C. Yds.	2,187
Bricks in surki mortar	C. Ft.	9,072
Stone slabs, 3" thick	S. Ft.	482
Covering slabs of tunnel (6" with sides dressed to make close joints)	Do	842
Plastering	Sq.	25·31
Pointing	Do	10·32
Clay paddling	C. Yds.	87
Earthwork	Do	1,240
Turfing	S. Yds.	1059+No. 5
Clearing site, removing trees, &c.	Item.	1
Baling water	Do	2
Rough stone work (lead 4½ miles)	C. Yds.	132
Stone slabs, 6" thick	S. Ft.	512
Concrete	C. Ft.	213
Rough stone (lead 3½ miles)	C. Yd.	44
Do work	Do	35
Rough stone work	Do	110
Pointing joints of covering slabs	Sq.	0·48
Guard stones	No.	4
Slab sluices as per type design	Do	7

R. T. SCALDWELL,
Executive Engineer.